



ADDENDUM #1 INFORMAL BID 2016-111

KITSAP COUNTY PARKS AND RECREATION KITSAP SUN PAVILION ROOF REPAIRS & PAINTING

TO: All Respondents
FROM: Colby Wattling, Buyer
CLOSING DATE: MARCH 22, 2016 at 3:00PM (UNCHANGED)
REF NO.: 2016-111
DATE: March 10, 2016

The following are **questions** and **answers** asked during the March 10, 2016 site walk. Additionally please note this project needs to be completed on a dry day so that the tape seals and the coating sticks to the roof.

- Q1:** Does this project cover the entire roof? **A1:** Yes
- Q2:** Where is the leaking? **A2:** Along the seam of the main building and attached storage building.
- Q3:** What material should we use to coat the roof? **A3:** After asking our facilities manager, he suggested Inland Coating, mineral base would be the best option.
- Q4:** How many square feet is the roof? **A4:** 40,000 SF
- Q5:** What are the dimensions of the building? **A5:** 151' x 251' main building and attached storage facility is 35' x 174'
- Q6:** Does this project include the lower portion of the roof as well? **A6:** Yes
- Q7:** Does this project include the flat portions of the roof where the HVAC systems are located? **A7:** Yes
- Q8:** What color is it going to be painted? **A8:** Teal
- Q9:** Are there tie offs on the roof? **A9:** Yes
- Q10:** What size width sealing tape should we use? **A10:** At least 4 inch.
- Q11:** What is the timeline? **A11:** Completion of this project must be no later than end of July. Work will need to not interrupt events and must work around other scheduled projects in the area.
- Q13:** Do you want a warranty? **A13:** Yes, 10 years.

There are no other changes to the original specifications other than what is changed by Addendum 1.

Acknowledgement of receipt of this and all ADDENDA are required

END OF ADDENDUM #1