

**ADDENDUM #2**  
**FORMAL BID #2016-156**

**KITSAP COUNTY PUBLIC WORKS WASTEWATER DIVISION**  
**MANCHESTER PUMP STATIONS**  
**45, 46, & 47 AND**  
**BEACH LINES REHABILITATION**

**September 29, 2016**

**TO:** All Respondents  
**FROM:** Colby Wattling, Buyer  
**CLOSING DATE:** October 6, 2016 at 3:00 PM (CHANGED PER ADDENDUM #1)  
**REF NO.:** Manchester Pump Stations 45, 46, & 47 and Beach Lines Rehabilitation  
**DATE:** September 29, 2016

---

The purpose of this addendum is to modify the Contract Documents for the referenced project. This addendum shall become a part of these Contract Documents. Bidder shall acknowledge receipt of this 5 page addendum (including attachments) on the Bid Form.

**VOLUME 1 OF 2 OF THE CONTRACT DOCUMENTS IS MODIFIED AS FOLLOWS:**

**BID PROCEDURES AND CONDITIONS**

**BID PROPOSAL**

Item 1. REVISE No. 4 in Summary of Bid Documentation as follows:

4. Bidder Information
  - a. Bidder Responsibility Checklist
  - b. Subcontractor Responsibility Checklist
  - c. ~~Project References~~

**BID SCHEDULE**

Item 2. REPLACE Page 11 of the Bid Proposal with the attached Revised Bid Proposal Page 11. Note revision to Bid Item 23D and addition of Bid Item 26D.

**BIDDER INFORMATION**

Item 3. REVISE forth column in Bidder Information as follows:

Present gross dollar amount of ~~contracts not yet completed~~ remaining to be completed of work under contract:

**BIDDER’S CHECKLIST**

Item 4. REVISE No. 9.d in Bidder’s Checklist as follows:

- d. Bidder Information
  - i. Bidder Responsibility Checklist
  - ii. Subcontractor Responsibility Checklist
  - iii. ~~Project References~~

**WSDOT DIVISION 1 – SPECIAL PROVISIONS**

**1-07.5(5) Noise Restrictions**

Item 5. REVISE the first paragraph to read as follows:

The Contractor shall comply with all local controls and noise level rules, specified requirements, regulations and ordinances which apply to any work performed pursuant to the Contract. If the requirements of this Section are more restrictive than those of the local regulations or specified in Section 02 22 29, the requirements of this Section shall govern.

**1-09.2(7) Bid Item Descriptions for Measurement and Payment**

Item 6. REVISE the Measure/Payment Description for Bid Items 22D and 23D as follows:

22D	Cured-In-Place Pipe (CIPP)	The unit price shall include all work, materials, tools, labor and equipment necessary and incidental to furnishing, installing and placing in approved service a CIPP in accordance with the specifications. Measurement for length shall be made along the centerline of the pipe from inside edge to inside edge of manhole. Items of the work include, but are not limited to safety measures and traffic control, pre-installation cleaning and Closed Circuit Television (CCTV) inspection of sewer main to be lined, root cutting and clearing sewer main of any protrusion/obstruction that might prevent the insertion of the liner, interior pipe repair to enable insertion of the liner, trimming of CIPP at manholes, <del>installation of a Top Hat at each service connection, as well as and the reinstatement and reconnection of the service connections,</del> all testing and CCTV inspection of all CIPP installed.
-----	----------------------------	--

23D	Sewer Lateral Rehabilitation (Allowance)*	The unit price shall include all work, materials, tools, labor and equipment necessary to rehabilitate an existing sewer lateral with CIPP starting from the new Top Hat connection at the existing beach sewer main and including but not limited to, a new cleanout at the home per Detail 3/C-4, above-ground locates, CCTV inspection, digs/repair of lateral prior to lining, temporary sewer bypassing if required by specifications, and CIPP lining of lateral (assume 100 LF per lateral, 6-inch diameter lateral).
-----	--	--

Item 7. ADD the following Bid Item to the end of the table in Section 1-09.2(7):

<u>26D</u>	<u>Top Hats</u>	<u>The unit price shall include all work, materials, tools, labor and equipment necessary and incidental to furnishing, installing and placing in approved service a Top Hat in accordance with the specifications. Items of the work include, but are not limited to safety measures and traffic control, installation of a Top Hat at each service connection, as well as and the reinstatement and reconnection of the service connections.</u>
------------	-----------------	--

**1-09.9(2) Contracting Agency’s Right to Withhold and Disburse Monies Due**

Item 8. REVISE No. 7 to read as follows:

- 7. For overtime work performed by the Engineer or Contracting Agency personnel (See Section ~~4-08.1(4)~~ 1-08.0(3)).

Item 9. REVISE No 9.a to read as follows:

- a. Failure of the Contractor to protect survey stakes, markers, etc., or to provide adequate survey work as required by Section ~~4-05.5~~ 1-05.4.

Item 10. REVISE No 9.b to read as follows:

- b. Failure of the Contractor to correct defective or unauthorized equipment or work (Section ~~4-05.8~~ 1-05.7).

**CSI SPECIFICATIONS**

**SECTION 02 22 29 CONSTRUCTION NOISE AND VIBRATION CONTROL**

Item 11. REVISE Paragraph 1.03.A.5 to read as follows:

- 5. A Construction Vibration Assessment performed in accordance with the guidance in Chapter 12 of the FTA Transit Noise and Vibration Impact Assessment Manual (~~April 1995~~ May 2006) for construction activities. The assessment shall include the independent Professional Engineer’s recommendations for vibration level restrictions, specific to each structure/feature being monitored.

Item 12. REVISE Paragraph 1.03.A.6 to read as follows:

6. A Construction Noise Assessment performed in accordance with the guidance in Chapter 12 of the FTA Transit Noise and Vibration Impact Assessment Manual (~~April 1995~~ May 2006) for construction activities. The assessment shall include the independent Professional Engineer's recommendations for noise level restrictions.

Item 13. REVISE Paragraph 3.03.A to read as follows:

- A. Identified noise-sensitive receptors likely to be impacted by construction ~~may~~ shall include, but are not limited to:

Item 14. REVISE Paragraph 3.05.A to read as follows:

- A. Identified ground vibration sensitive receptors likely to be impacted by construction ~~may~~ shall include, but are not limited to:

### **SECTION 33 01 30.72 CURED-IN-PLACE PIPE (CIPP) LINING**

Item 15. ADD the following to Paragraph 3.04 Lateral CIPP Installation:

- E. Lateral CIPP installation shall be performed when directed by the Engineer or Construction Manager and paid for under Bid Item 23D, Sewer Lateral Rehabilitation.

### **VOLUME 2 OF 2 OF THE CONTRACT DOCUMENTS IS MODIFIED AS FOLLOWS:**

Item 16. Drawing R47-1: REVISE the following callout pointing to the gravel surfacing to read as follows:

*From* REMOVE TOP 6" OF EX GROUND AND REPLACE WITH 1 1/4" CLEAN CRUSHED ROCK, PER DETAIL 2/R-1

*To* REMOVE TOP 6" OF EX GROUND AND REPLACE WITH 1 1/4" CLEAN CRUSHED ROCK PER DETAIL 2/R-1, PROVIDE AND INSTALL NONWOVEN GEOTEXTILE FOR SOIL STABILIZATION (TABLE 3) IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS BETWEEN THE NATIVE AND CRUSHED ROCK

Attachments For:

Item 2. Revised Bid Proposal Page 11

**End Addendum #2**

**Schedule D – Beach Lines Rehabilitation**

Item No.	Ref. Section	Est. Quantity	Unit Price (in words)	Unit Price (in Numbers)	Extended Amount (Qty x Unit Price) (in numbers)
22D. Cured-In-Place Pipe (CIPP)	Div. 33	3,300 LF		\$ _____	\$ _____
23D. Sewer Lateral Rehabilitation (Allowance)*	Div. 33	10 EA		\$ _____	\$ _____
24D. Beach Lines Manhole Rehabilitation	Varies	1 LS		\$ _____	\$ _____
25D. Beach Debris Removal (Allowance)*	Div. 2	10 TN		\$ _____	\$ _____
26D. Top Hats	Div. 33	45 EA		\$ _____	\$ _____
<b>Subtotal of Schedule D Bid Items</b>				\$ _____	
<b>Sales Tax @ 8.7%</b>				\$ _____	
<b>Total for Schedule D</b>				\$ _____	
<b>TOTAL FOR SCHEDULES A, B, C &amp; D WITH SALES TAX</b>				\$ _____	

\*Allowance - For the purpose of establishing a common basis for evaluating bids, an arbitrary quantity for this item has been shown on the bid form and does not necessarily represent the quantity that may be necessary for the work. The Variation in Estimated Quantities provisions of Section 1-04.6 of the Standard Specifications shall not apply to this item. Quantities will be determined in the field as work progresses.